

Wetlands application for:

Sidewalk improvements along the front of 1936-1940 Main Street

The project consists of removing lawn area and bituminous driveway aprons adjacent to the easterly curb of Main Street and installing a 5 feet wide concrete sidewalk to connect the missing sidewalk between existing sidewalks north and south of this area.

The volume of material to be removed from the upland review area approximately equals the amount of concrete sidewalk and base material to be installed and proposed grading on each side of the proposed sidewalk to meet existing grades. The volume of material to be installed in the wetlands area is for minor grading from the proposed sidewalk to the toe of slope.

The scope of work is approximately limited to the area within the street right-of way and a portion of the front lawns of the abutting home sites.

The project is anticipated to be completed by the end of November 2022.

With the implementation of soil erosion and sediment control devices, there will be virtually no environmental impact.

No other alternatives were considered as this project will connect the missing sidewalk between existing sidewalks.

This project will help improve the community by providing a safe means of pedestrian access to and from the nearby Churchill Park, Clem Lemire recreational complex and the rest of the neighborhood.