


OWNER / DEVELOPER:
JAMES CAMPBELL
109 STAMM ROAD
NEWINGTON, CT 06111
(860) 666-2696

LAND SURVEYING - LAND PLANNING:
THE BONGIOVANNI GROUP, INC.
170 PANE ROAD
NEWINGTON, CT 06111
(860) 666-0134

CIVIL ENGINEERING:
WESTON & SAMPSON
712 BROOK STREET, SUITE 103
ROCKY HILL, CT 06067
(860) 513-1473

DRAWING INDEX

SHEET 1	EXISTING CONDITIONS PLAN
SHEET 2	LAYOUT, LIGHTING & PLANTING PLAN
SHEET 3	GRADING AND STORMWATER MANAGEMENT PLAN
SHEET 4	EROSION & SEDIMENT CONTROL PLAN
SHEET 5	SITE DETAILS
SHEET 6	STORMWATER MANAGEMENT DETAILS
SHEET 7	STORMWATER MANAGEMENT DETAILS
SHEET 8	EROSION AND SEDIMENT CONTROL DETAILS
SHEET 9	EROSION AND SEDIMENT CONTROL DETAILS
SHEET 10	SITE DETAILS



GENERAL NOTES:


- ALL DISTURBED AREAS TO BE TOP SOILED AND SEEDED.
- LOT GRADING SHALL BE DONE TO PROVIDE SURFACE DRAINAGE AND PREVENT PONDING.
- SANITARY SEWERAGE AND WATER SERVICE TO BE PROVIDED BY THE METROPOLITAN DISTRICT COMMISSION.
- VERTICAL DATUM = NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88). HORIZONTAL DATUM = NORTH AMERICAN DATUM OF 1983 (NAD 83).
- ALL UTILITIES SHALL BE UNDERGROUND.
- CONSTRUCTION OF ANY IMPROVEMENTS SHOWN SHALL BE IN ACCORDANCE WITH CTDOT, FORM B18, AS AMENDED, "STANDARD SPECIFICATIONS FOR ROAD, BRIDGES AND INCIDENTAL CONSTRUCTION", "TOWN OF NEWINGTON SPECIFICATIONS FOR CONSTRUCTION OF ROADS", "TOWN OF NEWINGTON ZONING REGULATIONS", "TOWN OF NEWINGTON SUBDIVISION REGULATIONS" AND THE CONNECTICUT LANDSCAPE ASSOCIATION'S "STANDARD SPECIFICATIONS FOR PLANTING TREES, SHRUBS, VINES, ETC." ARE TO BE USED FOR CONSTRUCTION STANDARDS.
- SITE = 9,025 S.F. = 0.2072 ACRES.
- ACCESS TO THE SITE DURING CONSTRUCTION SHALL BE THROUGH THE CONSTRUCTION ENTRANCE AS SHOWN ON THE PLANS AND NO OTHER ACCESS SHALL BE ALLOWED.
- ACTUAL FIELD CONDITIONS MAY BE DIFFERENT OR CHANGED FROM THOSE CONDITIONS ASSUMED IN THE PREPARATION OF THIS PLAN AND IN SUCH CIRCUMSTANCES, THE TOWN ENGINEER MAY DIRECT THAT CERTAIN MODIFICATIONS OR AMENDMENTS BE EFFECTED AND CONSTRUCTED TO AMELIORATE SUCH CHANGED CONDITIONS.
- ALL PROPOSED CURBING TO BE EXTRUDED CONCRETE CURB.
- REBAR TO BE SET AT THE PROPERTY CORNERS.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND QUANTITIES PRIOR TO CONSTRUCTION.
- APPLICATION SHALL BE MADE TO TOWN OF NEWINGTON FOR EXCAVATION PERMIT PRIOR TO WORKING IN THE PUBLIC RIGHT OF WAY.
- FLOOD ZONE INFORMATION FROM "FIRM, FLOOD INSURANCE RATE MAP, HARTFORD COUNTY, CONNECTICUT (ALL JURISDICTIONS)", PANEL 492 OF 675, PANEL 0492F, MAP NUMBER 09003C0492F, EFFECTIVE DATE: SEPTEMBER 26, 2008, FEDERAL EMERGENCY MANAGEMENT AGENCY".
- THE CONNECTICUT DEEP NATURAL DIVERSITY DATABASE HAS BEEN REVIEWED AND THERE ARE NO AREAS OF STATE OR FEDERAL LISTED SPECIES AND NO CRITICAL HABITAT AREAS ON THE PROPERTY.
- THERE IS NO OUTSIDE STORAGE PROPOSED FOR THIS SITE.
- TOWN OF NEWINGTON DRAINAGE AGREEMENT SHALL BE REQUIRED PRIOR TO CONNECTION TO THE TOWN OF NEWINGTON STORMWATER SYSTEM.

APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as
 Petition # _____ at the TPZ meeting on _____
 _____ Date _____ Chairman _____

LEGEND	
PROPERTY LINE	---
LOT LINE	- - -
OVERHEAD WIRES	/ / /
WATER MAIN	W
GUARD RAIL	—
ELEVATION CONTOUR	—
APPROX. LIMIT INLAND WETLANDS FROM TOWN MAPPING	V V V
CATCH BASIN	□
MANHOLE	●
UTILITY POLE	Q
SPOT ELEVATION	X
BITUMINOUS	BIT.
SIDE YARD	S.Y.
FRONT YARD	F.Y.
REAR YARD	R.Y.

SOIL TYPE	
SOIL NUMBER	NAME
9	Scitico, Shaker, and Maybld soils
87D	Wethersfield loam, 15 to 25 percent slopes



THE BONGIOVANNI GROUP, INC.
 170 PANE ROAD
 NEWINGTON, CT 06111
 TEL (860) 666-0134
 FAX (860) 666-3830

3-20-24

ADDRESS TOWN COMMENTS

REFERENCE MAPS:

- "MAP OF PROPERTY OF ROBERT YAGLowski, LOT 205 & PART OF LOT 206 CARR AVE., NEWINGTON, CONNECTICUT", DATE: 7-11-89, SCALE: 1"=20', BY THE BONGIOVANNI GROUP, INC., LAND SURVEYORS.
- "SITE PLAN, ZONING LOCATION SURVEY, PREPARED FOR CHRISTOPHER TURNER, 165 CARR AVENUE, NEWINGTON, CONNECTICUT", DATE: 8-27-98, SCALE: 1"=20', REVISED THROUGH 4-19-01, BY THE BONGIOVANNI GROUP, INC.
- "PROSPERITY HEIGHTS, NEWINGTON, HARTFORD CO., CONNECTICUT, OWNED BY JOHN H. CARR, FORMERLY OWNED BY ESTATE OF FLORA J. LUCE, SCALE 1"=100', OCTOBER 11, 1922, ERNEST W. BRANCH, CIVIL ENGINEER".
- "RIGHT OF WAY AND TRACK MAP, THE NEW YORK NEW HAVEN AND HARTFORD R.R. CO., OPERATED BY THE NEW YORK NEW HAVEN AND HARTFORD RR. CO., FROM NEW HAVEN TO SPRINGFIELD, STATION 1425+60 TO STATION 1478+40, TOWN OF NEW BRITAIN, NEWINGTON, STATE OF CONNECTICUT, SCALE: 1 IN.=100 FT., DATE JUNE 30, 1915".

NOTES:

1. THIS SURVEY HAS BEEN PREPARED PURSUANT TO THE REGULATIONS OF CONNECTICUT STATE AGENCIES SECTIONS 20-300b-1 THROUGH 20-300b-20, AS REVISED.

TYPE OF SURVEY: IMPROVEMENT LOCATION SURVEY

BOUNDARY DETERMINATION CATEGORY: RESURVEY

CLASS OF HORIZONTAL ACCURACY: A-2

CLASS OF TOPOGRAPHIC ACCURACY: T-2

2. HORIZONTAL DATUM IS BASED ON NAD83 DATUM.

3. ELEVATIONS ARE BASED ON NAVD88 DATUM.

4. THIS MAP IS VALID ONLY IF IT BEARS THE ORIGINAL SIGNATURE AND EMBOSSED SEAL OF THE UNDERSIGNED LAND SURVEYOR.


TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.


SURVEYOR'S SIGNATURE _____ DATE _____ LICENSE NUMBER _____

SITE PLAN PROPERTY OF JAMES CAMPBELL
 161 CARR AVENUE
 NEWINGTON, CONNECTICUT

EXISTING CONDITIONS PLAN

Sheet 1 10 of





SOIL TYPE	
SOIL NUMBER	NAME
9	Scitico, Shaker, and Maybld soils
87D	Wethersfield loam, 15 to 25 percent slopes

GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

THIS DRAWING HAS BEEN PREPARED BASED, IN PART, ON INFORMATION PROVIDED BY OTHER PERSONS. THE LOCATION OF UNDERGROUND SERVICES WE CAN NOT VERIFY THE ACCURACY OF THIS INFORMATION AND SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH MAY BE INCORPORATED HEREIN AS A RESULT.
INDICATED UNDERGROUND UTILITIES ARE BASED ON AVAILABLE DATA. THE LOCATIONS ARE APPROXIMATE AND ALL UTILITIES MAY NOT BE SHOWN.
CALL "CALL B-4-U DIG" AT 1-800-922-4455 PRIOR TO ANY EXCAVATION.

APPROVED BY THE NEWINGTON
CONSERVATION COMMISSION

PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as
Petition # _____ at the TPZ meeting on _____
Date _____ Chairman _____

NOTES:

1. THIS SURVEY HAS BEEN PREPARED PURSUANT TO THE REGULATIONS OF CONNECTICUT STATE AGENCIES SECTIONS 20-300b-1 THROUGH 20-300b-20 AS REvised.

TYPE OF SURVEY: IMPROVEMENT LOCATION SURVEY

BOUNDARY DETERMINATION CATEGORY: RESURVEY

CLASS OF HORIZONTAL ACCURACY: A-2

CLASS OF TOPOGRAPHIC ACCURACY: T-2

2. HORIZONTAL DATUM IS BASED ON NAD83 DATUM.

3. ELEVATIONS ARE BASED ON NAVD88 DATUM.

4. THIS MAP IS VALID ONLY IF IT BEARS THE ORIGINAL SIGNATURE AND EMBOSSED SEAL OF THE UNDERSIGNED LAND SURVEYOR.


TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

SURVEYOR'S SIGNATURE _____ DATE _____
LICENCE NUMBER _____

SITE PLAN
PROPERTY OF
JAMES CAMPBELL
161 CARR AVENUE
NEWINGTON, CONNECTICUT


EROSION &
SEDIMENT
CONTROL

Sheet 4
of 10




Weston & Sampson
712 Broad Street, Suite 103
Newington, CT 06111
860.413.1413
www.westonsampson.com

Date: 1-15-24
Drawn: BM
Scale: 1" = 20'
Checked: AB
Date: _____
Revision: _____
Address: _____
Comments: _____
3-20-24




BITUMINOUS CONCRETE PARKING SECTION

SUBJECT TO ADJUSTMENT DUE TO FIELD CONDITIONS
not to scale




EXTRUDED CONCRETE CURBING

NOT TO SCALE



PERMANENT TRENCH PAVEMENT REPLACEMENT DETAIL

N.T.S.



TEMPORARY TRENCH PAVEMENT REPLACEMENT DETAIL

N.T.S.

SLIM12YW

Project: _____ Type: _____
Prepared By: _____ Date: _____

Driver Info

Type	Constant Current	Watts	LED Info
120V	0.13A	12W	Color Temp 3000K (Warm)
208V	0.08A		Color Accuracy 72 CRI
240V	0.07A		L70 Lifespan 100,000 Hours
277V	0.06A		Lumens 2,006 lm
			Input Watts 15W
			Efficacy 133.7

Color: White Weight: 4.1 lbs

RAB

SLIM18YW/PC

Project: _____ Type: _____
Prepared By: _____ Date: _____

Driver Info


Type	Constant Current	Watts	LED Info
120V	0.20A	18W	Color Temp 3000K (Warm)
208V	N/A		Color Accuracy 72 CRI
240V	N/A		L70 Lifespan 100,000 Hours
277V	N/A		Lumens 2,695 lm
			Input Watts 20.9W
			Efficacy 128.9

Color: White Weight: 4.1 lbs

RAB



WALL PACK LIGHTING DETAIL – 12W

WALL PACK LIGHTING DETAIL – 18W



ELECTRIC, TELECOMM AND GAS TRENCH DETAIL

NOT TO SCALE



APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as
Petition # _____ at the TPZ meeting on _____
Date _____ Chairman _____

SITE PLAN PROPERTY OF JAMES CAMPBELL
161 CARR AVENUE
NEWINGTON, CONNECTICUT

SITE DETAILS

Sheet 5 of 10

B61
THE BORGIGNE GROUP, INC.
170 Pine Road
Newington, Conn. 06111
(860) 666-3830

Date: 1-15-24	Scale: AS SHOWN
Drawn: Bml	Checked: _____
Revision: _____	Date: _____
ADDRESS TOWN COMMENTS	

Sheet 5 of 10


89124

5 of 10

ACCEPTABLE FILL MATERIALS: STORMTECH MC-3500 CHAMBER SYSTEMS


MATERIAL LOCATION		DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTION AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE ^{2,3}

PLEASE NOTE:
1. THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
2. STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERS WITH A VIBRATORY COMPACTOR.
3. WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
4. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



SUBGRADE DETENTION SYSTEM (A) SCHEMATIC

SCALE: N.T.S.



OUTLET CONTROL STRUCTURE (OCS4) AND PIPING DETAIL


SCALE: N.T.S.

NOTES:

1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 45x76 DESIGNATION SS.
2. MC-3500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
3. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
4. REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/FT%. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT Elevated TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

MC-3500 CROSS SECTION DETAIL

SCALE: N.T.S.



ISOLATOR ROW DETAIL

SCALE: N.T.S.

APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as Petition # _____ at the TPZ meeting on _____
Date _____
Chairman _____

SITE PLAN PROPERTY OF JAMES CAMPBELL
161 CARR AVENUE
NEWINGTON, CONNECTICUT

STORMWATER MANAGEMENT DETAILS

Sheet 7 of 10

Weston@Sampson
712 Broad Street, Suite 103
Rocky Hill, CT 06067
860.515.1419
www.westonsampson.com


BGI
THE BONGIOVANNI GROUP, INC.
LAND SURVEYORS
170 Main Street, Room 301
Newington, Conn. 06111
TEL (860) 666-3830
FAX (860) 666-0134

Scale: As Shown
Checked: Ab
Date: _____
Revision: _____
Address Town Comments: _____

Date: 1-15-24
Drawn: BM
Revision: _____

Address Town Comments: _____


89124



PLAN SECTION

NOTES:

1. BALES SHALL BE TRENCHED 4" INTO GROUND (FULL WIDTH OF BALE).
2. PLACE HAY BALE SUCH THAT TWINE/BINDING WIRE IS PARALLEL TO EXISTING GROUND.




NOTE: TO BE USED IN LOCATIONS WHERE THE EXISTING GROUND SLOPES IN TOWARD THE TOE OF SLOPE

NOTE: TO BE USED IN LOCATIONS WHERE THE EXISTING GROUND SLOPES AWAY FROM THE TOE OF SLOPE

STRAW BALE DETAIL


N.T.S.



SILT FENCE DETAIL

N.T.S.


1. SET POSTS AND EXCAVATE A 6"x6" TRENCH. SET POSTS DOWNSLOPE.
2. ATTACH GEOTEXTILE TO THE POSTS AND EXTEND IT TO THE TRENCH. MINIMUM LENGTH OF GEOTEXTILE IS 15'. MINIMUM SPACING OF POSTS IS 10'. JOINTS ONLY SUPPORT POSTS WITH A MINIMUM 6" OVERLAP.
3. BACKFILL THE TRENCH AND COMPACT THE EXCAVATED SOIL.



PLAN


TOE OF SLOPE LOCATION

NOT TO SCALE



TEMPORARY STOCKPILE DETAIL

N.T.S.




NOTES:

1. TRAP ROCK SHALL BE CTDOT NO. 3 STONE (M.01.01).
2. FILTER FABRIC SHALL BE PLACED BELOW STONE FOR EASE OF REMOVAL.

ANTI-TRACK PAD

N.T.S.



NOTES

1. INSTALL AND ANCHOR PER MANUFACTURER'S SPECIFICATIONS
2. SHALL BE INSTALLED IN FOREBAY, SWALE, AND WHERE SLOPES ARE 2:1 OR STEEPER.

VEGETATIVE SLOPE PROTECTION DETAIL

N.T.S.

APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as Petition # _____ at the TPZ meeting on _____
Date _____ Chairman _____

SITE PLAN
PROPERTY OF
JAMES CAMPBELL
161 CARR AVENUE
NEWINGTON, CONNECTICUT

EROSION &
SEDIMENT
DETAILS

Sheet 8 of 10
89124

Weston & Sampson
712 Broad Street, Suite 103
Newington, CT 06111
860.513.1473
www.westonsampson.com

BSI
THE BONGIOVANNI GROUP, INC.
LAND SURVEYORS
770 New Haven Avenue
Newington, Conn. 06111
TEL (860) 666-3830
FAX (860) 666-3830

Date: 1-15-24	Scale: AS SHOWN
Drawn: BLM	Checked: AB
Revision: _____	Date: _____
ADDRESS TOWN COMMENTS	

Sheet 8 of 10
89124

EROSION CONTROL NOTES

PROJECT DESCRIPTION

A COMMERCIAL ADDITION IS PROPOSED ON TWO PARCELS OF LAND LOCATED AT 46 & 48 COMMERCE COURT, IN NEWINGTON, CONNECTICUT. IN ADDITION TO THE NEW COMMERCIAL SPACE, THE PROJECT SHALL INCLUDE CONSTRUCTION OF ADDITIONAL PARKING AREA, STORMWATER MANAGEMENT SYSTEM, UTILITIES, TURF ESTABLISHMENT, AND EROSION & SEDIMENTATION CONTROL MEASURES.

WATER EROSION CONTROL MEASURES

EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THIS EROSION AND SEDIMENT CONTROL PLAN AND THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL (2002). THE CONTRACTOR FOR THE PROJECT SHALL MAINTAIN A COPY OF THIS EROSION AND SEDIMENT CONTROL PLAN AND THE CONNECTICUT GUIDELINES ON-SITE DURING CONSTRUCTION ACTIVITIES.

EROSION AND SEDIMENT CONTROL MEASURES SHALL CONSIST OF STRAW BALES, SILT SACK (INLET PROTECTION), WOVEN FABRIC (SILT FENCE), CONSTRUCTION ENTRANCE, TEMPORARY SEDIMENT TRAP, TEMPORARY SWALES (IF REQUIRED), AND EROSION CONTROL BLANKETS.

ALL MATERIAL SHALL BE NEW AND FREE FROM DEFECTS THAT WOULD COMPROMISE THE EFFECTIVENESS OF THE CONTROL MEASURES. AFTER COMPLETION, ALL MATERIAL SHALL BE DISPOSED OF PROPERLY. LOCATION OF EROSION AND SEDIMENT CONTROL MEASURES CAN BE SEEN ON THE PHASED EROSION AND SEDIMENT CONTROL PLANS. NOTE ALL WATER CONTROL MEASURES SHALL BE LOCATED DOWN GRADIENT FROM DISTURBED AREAS. IF TOPSOIL IS TO BE STORED IN AN AREA NOT SHOWN ON THE SITE PLAN, DUE TO UNFORESEEN EVENTS, PRIOR TO STORING, THE DOWN-GRADIENT PERIMETER OF THE STORAGE AREA SHALL BE PROPERLY PROTECTED TO THE SPECIFICATIONS DETAILED ON THIS PLAN.

WIND EROSION CONTROL MEASURES

DURING DRY WEATHER CONDITIONS, DISTURBED AREAS SHALL BE PROTECTED AGAINST WIND EROSION. DUSTY AREAS SHALL BE SPRAYED WITH WATER TO PREVENT WIND-BORNE PARTICLES.

SEEDING

ALL DISTURBED AREAS SHALL BE RESTORED – REFER TO LANDSCAPE PLANS FOR APPLICABLE SEED MIX AND SOIL AMENDMENTS.

DEWATERING

IN THE EVENT DEWATERING IS REQUIRED, THE CONTRACTOR SHALL CONSTRUCT AND MAINTAIN A DEWATERING SETTLING BASIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EVALUATING THE REQUIRED DEWATERING RATES AND SIZING THE BASIN AS OUTLINED IN THE CONNECTICUT SOIL AND EROSION CONTROL GUIDELINES. THE DEWATERING BASINS SHALL BE LOCATED ON SITE AWAY AREAS WHERE SURFACE WATER IS DIRECTED AWAY FROM THE BASIN. DISCHARGE FROM THE BASIN SHALL BE DIRECTED AWAY FROM WETLAND AREAS AND SHALL NOT CREATE EROSION.

MAINTENANCE OF EROSION AND SEDIMENT CONTROLS

MAINTENANCE OF EROSION AND CONTROL SHALL BE COMPLETED IN ACCORDANCE WITH THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL (2002). THE CONTRACTOR SHALL MAINTAIN A COPY OF THE GUIDELINES ON-SITE AND REFER TO THE APPROPRIATE MAINTENANCE PROCEDURES THAT SHALL BE UTILIZED DURING THE CONSTRUCTION. A SUMMARY OF THE MAINTENANCE REQUIREMENTS FOR THE PROJECT IS SUMMARIZED BELOW.

DURING THIS TIME ALL EROSION AND SEDIMENT STRUCTURES SHALL BE MAINTAINED IN PROPER WORKING ORDER. DISTURBED AREAS SHALL BE KEPT TO A MINIMUM AND SHALL ONLY TAKE PLACE WHERE IMMEDIATELY REQUIRED TO FURTHER CONSTRUCTION. IT IS DESIRABLE FROM AN EROSION PREVENTION CONCERN TO MINIMIZE DISTURBED AREAS. FINAL GRADING AND SEEDING SHALL TAKE PLACE AS SOON AS PRACTICAL.

A RAIN GAUGE SHALL BE PLACED AT THE PROJECT IN A WORKABLE LOCATION AND MONITORED DURING RAINFALL PERIODS UNTIL ALL DISTURBED AREAS ARE STABILIZED. IN THE EVENT THERE IS A RAINFALL GREATER THAN 1/2" IN A 12 HOUR PERIOD, ALL EROSION CONTROL MEASURES SHALL BE CHECKED AND REPAIRED AS REQUIRED WITHIN 24-HOURS OF THAT RAIN EVENT. IF NO RAIN GAUGE IS USED, ALL EROSION CONTROL MEASURES SHALL BE CHECKED AFTER ALL RAINFALL EVENTS.

CONSTRUCTION ACCESS ROAD AND ENTRANCE:

CONSTRUCTION ACCESS ROAD SHALL BE INSPECTED AT THE COMPLETION OF EACH WORKING DAY. THE ACCESS ROAD AND ENTRANCE SHALL BE REPAIRED AND/OR TOP-DRESSED WITH ADDITIONAL AGGREGATE TO ELIMINATE RUTS AND PROVIDE A STABLE SURFACE FOR ENTERING AND EXITING THE PROJECT SITE. REMOVE ALL SEDIMENT SPILLED ON THE TRACKING PAD IMMEDIATELY TO AVOID TRACKING MATERIALS INTO EXISTING STREETS. ROADS ADJACENT TO THE CONSTRUCTION SHALL BE LEFT CLEAN AT THE END OF EACH WORKING DAY.

SILT FENCE AND STRAW BALES:

THESE FACILITIES SHALL BE INSPECTED A MINIMUM OF ONCE PER WEEK OR AS REQUIRED ABOVE, BASED ON RAINFALL AT THE PROJECT SITE. REPAIRS AND MAINTENANCE SHALL BE COMPLETED AS NEEDED TO MAINTAIN THE FACILITIES IN PROPER WORKING ORDER. ADDITIONAL SILT FENCE AND STRAW BALES SHALL BE ADDED AS NEEDED DURING THE PROJECT TO REPLACE FAILED SYSTEMS OR LIMIT OTHER AREAS OF EROSION ON THE SITE.

TEMPORARY BERMS/SWALES (AS NEEDED):

THE SWALE SHALL BE INSPECTED A MINIMUM OF ONCE PER WEEK OR AS REQUIRED ABOVE, BASED ON RAINFALL AT THE PROJECT SITE. REPAIRS AND MAINTENANCE SHALL BE COMPLETED AS NEEDED TO MAINTAIN THE FACILITIES IN PROPER WORKING ORDER. THE SWALE SHALL BE CLEANED AS REQUIRED AND ADDITIONAL STONE PROVIDED IN THE SWALE AS NEEDED.

TEMPORARY SEDIMENTATION TRAP(S):

THE SEDIMENTATION TRAP SHALL BE INSPECTED A MINIMUM OF ONCE PER WEEK OR AS REQUIRED ABOVE, BASED ON RAINFALL AT THE PROJECT SITE. REPAIRS AND MAINTENANCE SHALL BE COMPLETED AS NEEDED TO MAINTAIN THE FACILITY IN PROPER WORKING ORDER. THE SEDIMENTATION TRAP SHALL BE CLEANED WITH THE SEDIMENT ACCUMULATED EXCEEDS ONE HALF OF THE STORAGE CAPACITY OR WHEN THE DEPTH OF THE AVAILABLE WATER IS REDUCED TO LESS THAN 18-INCHES. THE CONTRACTOR SHALL INSTALL A MARKER STAKE IN 2 LOCATIONS WITHIN THE SEDIMENTATION TRAP FOR THE PURPOSE OF TRACKING SEDIMENT LEVELS WITHIN THE TRAP. DURING REMOVAL OF THE SEDIMENT THE CONTRACTOR SHALL FOLLOW ALL PROCEDURES OUTLINED IN THE CONNECTICUT GUIDELINES FOR SOIL AND EROSION CONTROL (2002). EXCAVATED SEDIMENTS SHALL BE STAGED AND SURROUNDED WITH STRAW BALES IN A MANNER SIMILAR TO STAGING FOR STOCKPILES.

A CHECK LIST (PROVIDED BY THE RESIDENT REPRESENTATIVE) SHALL BE FILLED OUT BY THE CONTRACTOR EVERY WEEK OR AFTER EACH RAINFALL EVENT OF 1/2" OR GREATER AS NOTED ABOVE.

GENERAL NOTES

ALL DISTURBED AREAS SHALL BE KEPT TO A MINIMUM. FINAL GRADING AND RESTORATION SHALL BE ACCOMPLISHED AS SOON AS PRACTICAL.

EROSION AND SEDIMENT CONTROL STRUCTURES SHALL BE INSTALLED PRIOR TO SITE WORK. IF IT IS NOT POSSIBLE TO DO SO, THE ENGINEER SHALL BE NOTIFIED IN ORDER TO MAINTAIN THE INTEGRITY OF DESIGN.

ALL CONTROL STRUCTURES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION AND REMOVED WHEN STABILIZATION HAS BEEN ATTAINED. IF THE PROPOSED CONTROL MEASURES ARE NOT SATISFACTORY, ADDITIONAL CONTROL MEASURES SHALL BE TAKEN.

ALL RUNOFF FROM THE DISTURBED AREA SHALL BE CONTROLLED AND FILTERED. NON-WOVEN SYNTHETIC FIBER FILTER FABRIC, STRAW BALES OR SILTATION FENCE SHALL BE USED IN THE AREAS SHOWN ON THE SITE PLAN AND INSTALLED AS SHOWN ON THIS PLAN.

THE CONTRACTOR MUST OBTAIN COPIES OF THE ZONING, WETLANDS PRIOR TO THE START OF WORK.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF SEDIMENT AND EROSION CONTROL MEASURES. THIS RESPONSIBILITY INCLUDES THE ACQUISITION OF MATERIALS, INSTALLATION, AND MAINTENANCE OF EROSION AND SEDIMENT STRUCTURES, THE COMMUNICATION AND DETAILED EXPLANATION TO ALL PEOPLE INVOLVED IN THE SITE WORK OF THE REQUIREMENTS AND OBJECTIVE OF THE EROSION AND SEDIMENT CONTROL MEASURES.

TWO (2) WEEKS PRIOR TO THE START OF WORK THE CONTRACTOR SHALL PROVIDE THE NAME AND PHONE NUMBER OF THE INDIVIDUAL RESPONSIBLE FOR IMPLEMENTATION OF THIS PLAN.

NOTIFY THE ZONING ENFORCEMENT OFFICER FOR INSPECTING THE EROSION AND SEDIMENTATION CONTROLS PRIOR TO BEGINNING EARTHWORK AND AFTER THE EROSION AND SEDIMENT MEASURES HAVE BEEN INSTALLED.

NOTIFY THE ZONING ENFORCEMENT OFFICER FOR INSPECTING THE NEW VEGETATION AFTER VEGETATION IS ESTABLISHED AND PRIOR TO REMOVING ANY EROSION AND SEDIMENT MEASURES.

THE ENGINEER, WESTON & SAMPSON ENGINEERS, INC. (860-616-6623) #712 BROOK STREET, ROCKY HILL, CT, 06067 SHALL BE NOTIFIED OF ANY PROPOSED ALTERATION TO THE EROSION AND SEDIMENT CONTROL PLAN, PRIOR TO ALTERING, IN ORDER TO ENSURE THE FEASIBILITY OF THE ADDITION, SUBTRACTION, OR CHANGE IN THE PLAN.

SEQUENCE FOR CONSTRUCTION, APPLICATION OF SOIL EROSION AND SEDIMENTATION CONTROL MEASURES, AND FINAL STABILIZATION OF THE PROJECT SITE



- CLEARLY DEFINE AND FLAG THE PROPERTY LIMITS OF AND LIMITS OF CONSTRUCTION.
- HOLD PRE-CONSTRUCTION MEETING (REMEMBER TO CALL BEFORE YOU DIG 1-800-922-4455)
- INSTALL PERIMETER EROSION AND SEDIMENTATION CONTROLS IN ACCORDANCE WITH THE EROSION CONTROL PLAN.
- CUT TREES WITHIN THE GRADING LIMITS AND REMOVE CUT WOOD. CHIP BRUSH AND REMOVE OFFSITE.
- EXCAVATE ALL STUMPS LOCATED IN THE STRUCTURAL AREAS AND REMOVE TO A DISPOSAL SITE OR STOCKPILE AREA TO BE CHIPPED.
- REMOVE AND STOCKPILE TOPSOIL AFTER EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN INSTALLED. MATERIAL MAY BE STOCKPILED OFF-SITE. THE TOPSOIL SHALL BE SEEDED IMMEDIATELY AFTER STOCK PILING IN ORDER TO STABILIZE THE SLOPE AND LIMIT SEDIMENT RUNOFF. STOCKPILED TOPSOIL SHALL BE SEEDED AND MULCHED WHEN IT IS TO BE STORED FOR MORE THAN 30 DAYS FROM TIME OF STOCKPILING.
- CUT OR FILL REMAINDER OF SITE TO ESTABLISH THE SUB-GRADE.
- INSTALL DRAINAGE FACILITIES STARTING AT THE OUTFALL AND PROCEEDING UPGRADE. PROTECT SUBGRADE SYSTEM FROM SEDIMENTATION ENTERING THE SYSTEM.
- EXCAVATE AND CONSTRUCT FOUNDATION OF BUILDING WITH APPROPRIATE STUBS/OPENINGS FOR UTILITIES. UPON COMPLETION, BACKFILL FOUNDATION WALLS.
- INSTALL UTILITIES AND CONNECT UTILITY SERVICE LATERALS TO BUILDING.
- PLACE, GRADE AND COMPACT THE PROCESSED AGGREGATE IN THE ROADWAY BASE.
- APPLY STABILIZATION MEASURES (TOPSOIL, SEEDING, ETC.) TO REMAINING DISTURBED AREAS IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL DETAILS.
- INSPECT AND CLEAN DRAINAGE SYSTEM AS NEEDED.
- TOPSOIL AND GRADE WHERE REQUIRED AND WITHIN 2 FEET OF PROPOSED CURBING.
- INSTALL FIRST COURSE OF BITUMINOUS CONCRETE PAVEMENT.
- UPON SUBSTANTIAL COMPLETION OF THE BUILDING, COMPLETE THE BALANCE OF SITE WORK AND STABILIZATION OF ALL OTHER DISTURBED AREAS.
- WHEN ALL OTHER WORK HAS BEEN COMPLETED, REPAIR AND SWEEP ALL PAVED AREAS FOR FINAL COURSE OF PAVING.
- INSTALL FINAL COURSE OF BITUMINOUS CONCRETE PAVEMENT.
- INSTALL BITUMINOUS CURBING (IF REQUIRED) AS SHOWN ON PLANS.
- INSTALL PLANTINGS, FINE GRADE, RAKE, SEED, AND MULCH.
- INSPECT DRAINAGE SYSTEM AND CLEAN AFTER PAVING AND LANDSCAPING ARE COMPLETE.
- AFTER ENTIRE SITE IS STABILIZED IN ACCORDANCE WITH THE APPLICABLE EROSION AND SEDIMENT CONTROL MEASURES, REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS (E.G. SILT FENCES).

SEDIMENTATION AND EROSION AND CONTROL MAINTENANCE PROCEDURES

ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE INSPECTED DURING CONSTRUCTION ON A WEEKLY BASIS, AND FOLLOWING ALL STORMS, BY THE RESIDENT REPRESENTATIVE. THE CONTRACTOR SHALL MAINTAIN AND MAKE REPAIRS AND REMOVE SEDIMENT IF IT HAS ACCUMULATED TO A DEPTH OF 1/2 THE HEIGHT OF THE HAYBALES, SILT FENCE, CATCH BASIN INSERTS, AS INSTALLED. THE CONTRACTOR HAS THE OPTION TO INSTALL A NEW ROW OF HAYBALES OR SILT FENCE BEHIND THE SEDIMENTED CONTROLS. THE CONTRACTOR SHALL MAINTAIN AND MAKE REPAIRS AND REMOVE SEDIMENT AS REQUESTED BY THE RESIDENT REPRESENTATIVE. THIS WORK SHALL BE PERFORMED WITHIN 24 HOURS OF THE REQUEST AND THERE SHALL BE NO SEPARATE PAYMENT FOR THIS MAINTENANCE. WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED OR HAVE TEMPORARILY BEEN SUSPENDED FOR MORE THAN THIRTY DAYS, OR WHEN FINAL GRADES HAVE BEEN REACHED IN ANY PORTION OF THE SITE, STABILIZATION PRACTICES SHALL BE IMPLEMENTED WITHIN 7 DAYS.

THE CONTRACTOR SHALL CLEAN SEDIMENT AND DEBRIS FROM ALL DRAINAGE STRUCTURES, AND PIPES AT THE COMPLETION OF CONSTRUCTION, AND AS REQUESTED BY THE RESIDENT REPRESENTATIVE TO KEEP THE SYSTEM FUNCTIONING PROPERLY DURING CONSTRUCTION.

FOLLOWING COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL REPAIR ALL ERODED AREAS AND ENSURE A GOOD STAND OF TURF IS ESTABLISHED THROUGHOUT. THE CONTRACTOR SHALL REPAIR ALL ERODED OR DISPLACED RIPRAP, AND CLEAN SEDIMENT COVERED STONES.



NOTES:

1. GEOTEXTILE BAG MATERIAL SHALL BE A NON-WOVEN MATERIAL.
2. DO NOT OVER PRESSURIZE BAG OR USE BEYOND CAPACITY.
3. LOCATE DISCHARGE SITE ON FLAT UPLAND AREAS AS FAR AWAY AS POSSIBLE FROM STREAMS, WETLANDS, AND OTHER RESOURCES AND POINTS OF CONCENTRATED FLOW.
4. DOWN-GRADIENT FROM RECEIVING AREA MUST BE WELL VEGETATED OR OTHERWISE STABLE FROM EROSION, E.G., FOREST FLOOR OR COARSE GRAVEL/STONE.
5. LOCATION OF DEWATERING BAG SHALL BE DETERMINED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY ENGINEER PRIOR TO USE.

GEOTEXTILE DEWATERING BAG
N.T.S.

APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as Petition # _____ at the TPZ meeting on _____
Date _____
Chairman _____

SITE PLAN PROPERTY OF	
JAMES CAMPBELL	
161 CARR AVENUE	
NEWINGTON, CONNECTICUT	
EROSION & SEDIMENT CONTROL DETAILS	

OPERATION AND MAINTENANCE PLAN

GENERAL

This section of the plan presents the operation and maintenance plan for the erosion and sediment control measures during construction and for the proposed stormwater management system. It also provides guidelines for when the stormwater system should be cleaned and associated recordkeeping.

EROSION AND SEDIMENT CONTROL MEASURES

The erosion control measures include the following items:

- Compost Filter Tubes and Silt Fence
- Silt Sacks
- Anti-Tracking Pad
- Vegetative Stabilization
- Temporary Soil Stockpiles
- Dust Control

During construction, the Contractor will be responsible for the operation and maintenance of the erosion and control measures. During this time all erosion and sediment structures shall be maintained in proper working order. Disturbed areas shall be kept to a minimum and shall only take place where immediately required to further construction. It is desirable from an erosion prevention concern to minimize the total disturbed area at any one time. Final grading and seeding shall take place as soon as practical.

A rain gauge shall be placed at the project in a workable location and monitored during rainfall periods until all disturbed areas are stabilized. In the event there is a rainfall greater than 1/2" in a 12-hour period, all erosion control measures shall be checked and repaired as required. If no rain gauge is used, all erosion control measures shall be checked after all rainfall events. A checklist will be filled out by the contractor each week.

All soil erosion and sediment control measures shall be installed as shown on the proposed site plans. It is the intent of this plan that soil erosion measures are the first to be installed and the last to be removed. Surface waters on the project area are to be protected from degradation and sedimentation. If areas adjacent to the project area are jeopardized by construction, it shall be the owner's or contractor's responsibility to protect those properties.

Soil erosion measures shall be inspected weekly and after significant storm events. Make all necessary repairs to facilities as soon as possible. Silt fences and filter tube barriers, and construction swales which accumulate sediment and debris shall be cleaned and re-set.

MAINTENANCE SCHEDULES

The proposed site plan includes the following stormwater structures:

- Catch Basins with sumps, and Drainage Manholes
- Drainage Piping
- Subgrade detention chamber systems
- Outlet Control Structures

The Owner(s) will be responsible for the operation and maintenance of the stormwater structures located outside of the road right -of way. These structures are reflected in the attached Checklist. This Checklist will be utilized during the inspection and cleaning process and kept on file.

1. Catch Basins with sumps, Drainage Manholes (Includes Outlet Control Structure):

- Structures shall be completely cleaned of accumulated debris and sediments at the completion of construction.
- For the first year, structures shall be inspected on a quarterly basis.
- Any accumulated debris within the catch structures shall be removed and any repairs as required.
- From the second year onward, visual inspections shall occur twice per year, once in the spring and once in the fall, after fall cleanup of leaves has occurred.
- Accumulated debris within the structures shall be removed and repairs made as required.
- Accumulated sediments shall be removed at which time they are within 12 inches of the invert of the outlet pipe.
- Any additional maintenance required per the manufacturer's specifications shall also be completed.

2. Drainage Piping

- All storm drainage piping shall be completely flushed of debris and accumulated sediment at the completion of construction.
- Unless system performance indicates degradation of piping, comprehensive video inspection of storm drainage piping shall occur once every ten years.
- Any additional maintenance required per the manufacturer's specifications shall also be completed.

3. Subgrade Detention Systems

The Subgrade Detention Systems will have an Isolator Row which is wrapped in a specified filter fabric to trap sediment and will be inspected every three months through the inspection port and shall be cleaned once a year at a minimum. If during inspection, it is found that the sediment has accumulated within the Isolator Row, it shall be cleaned immediately with a jet-vac and accessed from the 24" HDPE manifold piping located at each end. The System's Isolator Row should be cleaned after the snow and ice removal seasons and before spring rainfall events.

3. Street Sweeping


The driveways/parking areas will be swept twice a year. Once after the winter season has ended and once during the fall season.

Disposal of Debris and Sediment:


All debris and sediment removed from the stormwater structures shall be disposed of in accordance with local regulations. There shall be no dumping of silt or debris into or in proximity to any inland wetlands.

Maintenance Records:

The Owner(s) must maintain all records (logs, invoices, reports, data, etc.) and have them readily available for inspection at all times.



NOTE:
SNOUT DETAILS SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL COORDINATE WITH MANUFACTURER FOR EXACT HOOD TYPE, SIZE, AND STRUCTURE WALL FOR INSTALLATION.



APPROVED BY THE NEWINGTON CONSERVATION COMMISSION
PETITION NO. _____
AT THE MEETING OF: _____
CHAIRMAN _____
DATE _____

Approved by the Newington Town Plan and Zoning Commission as	
Petition # _____ at the TPZ meeting on _____	
Date _____	Chairman _____

SITE PLAN PROPERTY OF JAMES CAMPBELL
161 CARR AVENUE
NEWINGTON, CONNECTICUT

SITE DETAILS
Sheet 10 of 10

Weston & Sampson
712 Broad Street Suite 103
Newington, CT 06111
860.515.1473
www.westonsampson.com

BMP, INC.
THE BORGIOANNI GROUP, INC.
LTD. SNOOT SNOOTS
770 Broad Street, Suite 103
Newington, Conn. 06111
TEL: (860) 668-1930
FAX: (860) 668-1930

Date: 1-15-24	Scale: AS SHOWN
Drawn: BIM	Checked: AB
Date: _____	
Revision: _____	
ADDRESS: TOWN: COMMENTS: _____	

Sheet 10 of 10

89124